

LOG PACKAGE LABOR LIST

Rip and install starter plate on the floor system. (Homeowner will supply starter plate.)

Lay out window & door openings, electrical outlets, and switches.

Drill out for electrical outlets and also cut out electrical switches and electrical outlets in log walls.

Cut and stack 6x8 D-logs, 13 courses, cut all notch and pass corners on site.

Install 1x2 expansion splines at the end of log joints, and window and door openings. (Splines provided by Quality Log Home Builders)

Furnish and install color caulking for log joints

Furnish and install 4x6 window and door buck framing

Provide fasteners and adhesives for window buck framing

Build and install stud pilasters to log walls where partition framing meets log wall. (Studs provided by homeowner.)

Remove tongues off top course of log.